



ÖRESUND



Client: Sudlink Contractors
Location: Sweden - Denmark
Construction Site: Cadiz Yard - Spain
Completion Date: July 1999
Contract Type: BOQ
Total Weight: 49 spans - 245,000 tons

Project Description: The project consists in construction of a road to link the cities of Copenhagen (Denmark) and Malmö (Sweden). The development starts with a submerged tunnel, emerging on an artificial island, which leads to a 7 km bridge.



Scope of Work: Our SOW consisted on the construction engineering, procurement, fabrication, load out & transportation of the 49 spans of composite steel/concrete structure. The final dimensions of each span were 25 meters x 140 meters, with a final total weight for the 49 spans of 245,000 Tons. The transportation was performed in 25 shipments (every 21 days) with 2 spans per shipment with each span weighing approximately 5,000 tons.

